

To upload please



CSK Himachal Pradesh Krishi Vishvavidyalaya
KRISHI VIGYAN KENDRA LAHAUL & SPITI , KUKUMSERI
Camp office at CSK HPKV, Palampur- 176 062 (H.P.)



No.QSD 5-1/23/CSKHPKV/KVK/Bud/- 663-669
Dated:- 13.12.2024

From

Programme Coordinator

To

Incharge, UNS
CSKHPKV-Palampur

Subject:

Quotations (NIQ for installation/fabrication of new 105 m² V shape polyhouse at KVK-Kukumseri, Lahaul & Spiti)

Sir,

In continuation to the quotations called vide this office letter No. QSD 5-1/23/CSKHPKV/KVK/Bud/576-82 dated 22.11.2024, fresh sealed quotations are again invited by the under signed as per works to be performed given below.

Description
<p>105 sqm V SHAPE POLYHOUSE (Even Span) :-</p> <p>Size: Area 105 m²(L=15 m and W=7m) and center height 4.5m Side height (2.5m), Span 2.5 m</p> <p>Frame structure: The structure should be made from galvanized steel square/round pipes (ISI marked) size 40mm x 40mm (foundation and vertical post) and 25mm /40mm roof arches and other posts Purling of 32 mm GI Pipes. IS class designated pipes to withstand wind loading of not less than 140-150 Km/ hour. The method of affixing the UV stabilized film to the frame should be strong enough to withstand similar wind velocities. The thickness of pipes should be greater than 2mm.</p> <p>Center Posts: 40 mm center posts should be provide along the length of greenhouse</p> <p>Buffer room with double door :2 m x 2 m</p> <p>Top roof cover with weld mesh wire 10 gage</p> <p>Poly film: The structures should be glazed with200 micron thickness, U.V. stabilized (anti fog, diffused and anti-dust) (Sheet shall be buried to minimum depth of 50 cm in the ground on the lower side to prevent migration of insect pest and seepage of water from outside etc)</p> <p>Fixing of cladding Materials: C type aluminum profile to fix shade net to the structure by means of self tapping screws. Weight of aluminum profile is 200-220 gm/meter. Self-drilling screw should be fixed on profile every 50 cm along the full length of the profile.</p> <p>Ventilations: The ventilation should be provided on two sides with roll over mechanism operated from ground for opening and closing of ventilations using 15 mm GI Pipe . The ventilation should start from 0.45 m from ground and height of ventilation should be 2.05 m along the two sides. The height of top ventilation should be 1m. All Two ventilation should be covered with UV Stabilized insect net of size 40 mesh.</p> <p>Shading: 50% Agro shading net, Green color UV stabilized on the below weld mesh, movable with manual rolling system should be provided.</p> <p>Foundations: Grouting of side poles in cement concrete 1:2:4 (45 x 45 x 60 cm) below ground level. Appropriate foundation depth (60 cm) to bear all pillars, R.C.C footings should be provided.</p> <p>Drip irrigation system: 1000 Ltr water tank , 1 hp pump dripper system, fogger system (brand netafim), fitting 16 mm lateral line and pvc 40 mm pipe disc filter rubber grommet including ventury system (for fertigation), motors/pumps should be fitted inside the polyhouse and covered for protection of water. Storage tank should be installed on raised concrete (brick) platform (Height 30 cm)</p>

The quotations should be strictly according to the terms and conditions as noted below otherwise the quotations will not be considered :-

TERMS & CONDITIONS:-

1. The rates should be quoted for installation of polyhouse at KVK, Kukumseri, Distt. Lahaul & Spiti-175142.
2. The price quoted should be inclusive of all charges viz. packing forwarding, insurance etc.
3. GST may be shown separately in the NIQ.
4. The quotations should be submitted only if the articles are in stock and can be supplied / installed promptly.
5. The delivery of stores is to be affected within the stipulated time otherwise the order will be cancelled forthwith at-risk expenses and the order will be placed to the next firm
6. The rates quoted should be strictly as per specifications stated above.
7. The interested parties can visit KVK, Kukumseri and assess the work to be executed.
8. **The last date for receipt of the quotations is 28.12.2024 at 11:00 am in the Camp office of Krishi Vigyan Kendra-Kukumseri, Directorate of Extension Education at CSK HPKV, Palampur, Distt.-Kangra 176062 (H.P.).**
9. The quotations received after the due date will not be considered
10. If the total value of new construction of polyhouse exceeds Rs. 1.00 Lakh the quotation should be accompanied with an earnest money i.e @ 2% of the estimated value of goods in shape of F.DR. duly pledged in the name of Comptroller, CSKHPKV, Palampur. The earned money if any, already deposited/laying in the office of the undersigned will not be considered for current quotation. The quotation without EMD will not be considered.
11. The performance security @ 5% of the whole amount of the total supply will be obtained from the successful bidder before placing the supply order. The earnest money already deposited shall form part of performance security.
12. **The quotations will be opened on 28.12.2024 at 3:00 pm in the Camp office of Krishi Vigyan Kendra-Kukumseri, Directorate of Extension Education at CSK HPKV, Palampur, Distt.-Kangra 176062 (H.P.), in which the representative of the bidder/firm can be present.**
13. **The quotations of the firm not following the above mentioned specifications, conditions/criteria will be cancelled, so be particular while filling the quotations, please.**
14. On the cover containing quotations please quote quotation due on 28.12.2024.

Yours faithfully


Programme Coordinator